



## MATERIALS OF CONSTRUCTION\*

TUBE ENDS - COPPER
HOSE & BRAID - BRONZE
90° ELBOW - COPPER
SPOOL - COPPER
\*OTHER MATERIALS AVAILABLE

## **NSF 372 - LEAD FREE**

The wetted surface of this product contacted by consumable water contains less than one quarter of one percent (0.25%) of lead by weight. Material complies with state codes and standards, where applicable, requiring reduced lead content.

NOTE: METRALOOPS 2" AND LARGER INSTALLED IN ANY ORIENTATION OTHER THAN HANGING DOWN <u>MUST</u> HAVE THE 180° RETURN SUPPORTED. (SEE INSTALLATION INSTRUCTIONS.)

## CONTACT FACTORY FOR ADDITIONAL SIZES AND MOVEMENTS. ALL DIMENSIONS IN INCHES.

QTY	SIZE	MODEL	MVMT	Α	В	PSI*	WT (LBS)	SPRING FORCE**	PROJECT INFO
	2.5	MLSPF30250	+/- 1.5	27	19.75	200	12	83	
	3	MLSPF30300	+/- 1.5	28	21.5	200	18	90	
	4	MLSPF30400	+/- 1.5	32	24.75	140	26	120	

<sup>\*</sup>Working pressure listed is the rating at 70° F. Contact factory for other pressure ratings at other temperatures and for steam applications.

CUSTOMER:\_\_\_\_\_\_
PROJECT:\_\_\_\_\_
ENGINEER:\_\_\_\_\_

REV.		DATE				
Met for pipes in		2323 W. HUBBARD ST. CHICAGO, IL 60612 TEL: 312-738-3800 FAX: 312-738-0415 WWW.METRAFLEX.COM				
PRESS FIT METRALOOP®						
SWE	AT ENDS, +/- 1	.5" MOVEMENT				

SWEAT ENDS, +/- 1.5" MOVEMENT DRAWN BY: **DKISH** DATE: **5/8/2015** 

APPROVED: JC DATE: 5/8/2015

SCALE: DRAWING NUMBER:

MLSPF30250-400

<sup>\*\*</sup>Spring force: The total force (Lbs) required to move the Metraloop its full rated movement for 150 PSI @ 70°F.