



MATERIALS OF CONSTRUCTION*

- TUBE ENDS - COPPER
- HOSE & BRAID - BRONZE
- 90° ELBOW - COPPER
- SPOOL - COPPER

*OTHER MATERIALS AVAILABLE

NSF 372 - LEAD FREE

The wetted surface of this product contacted by consumable water contains less than one quarter of one percent (0.25%) of lead by weight. Material complies with state codes and standards, where applicable, requiring reduced lead content.

NOTE: METRALOOPS 2" AND LARGER INSTALLED IN ANY ORIENTATION OTHER THAN HANGING DOWN MUST HAVE THE 180° RETURN SUPPORTED. (SEE INSTALLATION INSTRUCTIONS.)

CONTACT FACTORY FOR ADDITIONAL SIZES AND MOVEMENTS. ALL DIMENSIONS IN INCHES.

QTY	SIZE	MODEL	MVMT	A	B	PSI*	WT (LBS)	SPRING FORCE**	PROJECT INFO
	2.5	MLSPF80250	+/- 4	29	26.5	200	18	83	
	3	MLSPF80300	+/- 4	30.5	28.5	200	24	90	
	4	MLSPF80400	+/- 4	34	32	140	31	120	

*Working pressure listed is the rating at 70° F. Contact factory for other pressure ratings at other temperatures and for steam applications.

**Spring force: The total force (Lbs) required to move the Metraloop its full rated movement for 150 PSI @ 70°F.

CUSTOMER: _____

PROJECT: _____

ENGINEER: _____

REV.	DATE
2323 W. HUBBARD ST. CHICAGO, IL 60612 TEL: 312-738-3800 FAX: 312-738-0415 WWW.METRAFLEX.COM	
PRESS FIT METRALOOP® SWEAT ENDS, +/- 4" MOVEMENT	
DRAWN BY: DKISH	DATE: 5/8/2015
APPROVED: JC	DATE: 5/8/2015
SCALE: N/A	DRAWING NUMBER: MLSPF80250-400