



THIS FLEXIBLE PIPE SHOULD BE INSTALLED THE LENGTH SHOWN ON DRAWING. PIPING & EQUIPMENT CONNECTED BY THIS FLEXIBLE PIPE MUST BE PROPERLY ANCHORED AND/OR GUIDED. NOT INTENDED FOR TORSION.

QTY.	PIPE SIZE	A	B	C	D	E
	4"	12"	$\frac{7}{8}$ "	$\frac{3}{8}$ "	$\frac{9}{16}$ "	$5\frac{7}{8}$ "
	5	12	$\frac{7}{8}$	$\frac{3}{8}$	$\frac{9}{16}$	$6\frac{7}{8}$
	6	12	$\frac{7}{8}$	$\frac{3}{8}$	$\frac{5}{8}$	$7\frac{7}{8}$
	8	18	$\frac{7}{8}$	$\frac{3}{8}$	$\frac{3}{4}$	$9\frac{7}{8}$
	10	18	1	$\frac{3}{8}$	$\frac{3}{4}$	$12\frac{1}{8}$
	12	24	$1\frac{3}{16}$	$\frac{3}{8}$	$\frac{3}{4}$	$14\frac{1}{2}$

DESIGN DATA

MAX. PRESS. 150 P.S.I.
 MAX. TEMP. 180°F
 250°F

MATERIAL SPEC.

PIPE: DUCK & RUBBER 400
 BUTYL 400HT

CUSTOMER _____

PROJECT _____

ENGINEER _____

ARCHITECT _____

PRO OR P. O. NO. _____

THE
Metraflex
 COMPANY · CHICAGO ILLINOIS

DESCRIPTION:

400 FLEXIBLE PIPE

DRAWN BY L.K.	DATE 3-21-69	DRAWING NO.
------------------	-----------------	-------------